



EVERPURE® QL3 BH² SYSTEM

DELIVERS PREMIUM QUALITY WATER FOR COFFEE APPLICATIONS

QL3-BH² System: EV9272-00
BH2 Replacement Cartridge: EV9612-50



APPLICATIONS

Coffee
Low flow, medium volume brewers

FEATURES • BENEFITS

Proprietary Everpure® Micro-Pure® II media inhibits the growth of bacteria
Proportioned scale inhibitor feed
Engineered to always feed the correct amount of scale inhibitor into each volume of water
Precoat submicron technology reduces dirt and particles as small as 1/2-micron in size
Sanitary cartridge replacement is simple, quick and clean. Internal filter parts are never exposed to handling or contamination

Provides clear, fresh, premium quality ingredient water for great tasting coffee and beverages
Everpure's unique filter blend using activated carbon reduces chlorine taste and odor and other offensive contaminants
Saves energy by reducing scale buildup.
Dramatically prevents limescale from forming in brewers
Reduces health contaminants such as cysts
Increases holding time of coffee

INSTALLATION TIPS

Never use saddle valve for connection
Use 3/8" water line
Install vertically with cartridges hanging down
Allow 2-1/2" (6.35 cm) clearance below the cartridge for easy cartridge replacement
Flush BH² cartridge by running water through filter for three (3) minutes at full flow

OPERATION TIPS


Change cartridges on a regular six (6) month preventative maintenance program
Change cartridges when capacity is reached or when pressure falls below 10 psi (0.7 bar)
Service flow rate must not exceed 0.5 gpm (1.9 Lpm)
Always flush the filter cartridge at time of installation and cartridge change

SIZING

Service Flow Rate: Maximum 0.5 gpm (1.9 Lpm)
Rated Capacity: 3,000 gallons (11,350 L) or 6,000 pots

EVERPURE® QL3 BH² SYSTEM

EV9272-00



SPECIFICATIONS

Overall Dimensions

16.5" H x 3.75" W x 4" D
(41.9 x 9.5 x 10.1 cm)

Inlet Connection 3/8"

Outlet Connection 3/8"

Service Flow Rate

Maximum 0.5 gpm (1.9 Lpm)

Rated Capacity

3,000 gallons (11,350 L) or 6,000 pots

Pressure Requirements

10 – 125 psi (0.7 – 8.6 bar), non-shock

Temperature

35 – 100°F (2 – 38°C)

Electrical Connection

None

Shipping Weight

4 lbs. (1.8 kg)

Operating Weight

7 lbs. (3.1 kg)

The contaminants or other substances removed or reduced by this drinking water system are not necessarily in your water. Do not use with water that is microbiologically unsafe or of unknown quality without adequate disinfection before or after the system. Systems certified for cyst reduction may be used with disinfected water that may contain filterable cysts.

WARRANTY

Everpure water treatment systems by Pentair® (excluding replaceable elements) are covered by a limited warranty against defects in material and workmanship for a period of five years after date of purchase. Everpure replaceable elements (filter cartridges and water treatment cartridges) are covered by a limited warranty against defects in material and workmanship for a period of one year after date of purchase. See printed warranty for details. Pentair will provide a copy of the warranty upon request.



FILTRATION & PROCESSING SOLUTIONS

EVERPURE-SHURFLO WORLD HEADQUARTERS, 1040 MUIRFIELD DRIVE, HANOVER PARK, IL 60133 USA • WWW.EVERPURE.COM
800.942.1153 MAIN (US ONLY) • 630.307.3000 MAIN • 630.307.3030 FAX • CSEVERPURE@PENTAIR.COM EMAIL

EVERPURE-SHURFLO AUSTRALIA / NEW ZEALAND, 1-21 MONASH DRIVE, DANDENONG SOUTH, VIC, 3175, AUSTRALIA
1300.576.190 TEL • AU.EVERPURE@PENTAIR.COM EMAIL

EVERPURE-SHURFLO CHINA, 21F CLOUD 9 PLAZA, NO 1118, SHANGHAI, 200052, CHINA
86.21.3211.4588 TEL • 86.21.3211.4580 FAX • CHINA.WATER@PENTAIR.COM EMAIL

EVERPURE-SHURFLO INDIA, GREEN BOULEVARD, B-9/A, 7TH FLOOR - TOWER B SECTOR 62, NOIDA - 201301
91.120.419.9444 TEL • 91.120.419.9400 FAX • INDIACUSTOMER@PENTAIR.COM EMAIL

EVERPURE-SHURFLO EUROPE, PENTAIR WATER BELGIUM BVBA, INDUSTRIEPARK WOLFSTEE, TOEKOMSTLAAN, 30 B-2200 HERENTALS, BELGIUM
+32.(0).14.283.500 TEL • +32.(0).14.283.505 FAX • SALES@EVERPURE-EUROPE.COM EMAIL

EVERPURE-SHURFLO JAPAN INC., HASHIMOTO MN BLDG. 7F, 3-25-1 HASHIMOTO, MIDORI-KU, SAGAMIHARA-SHI KANAGAWA 252-0143, JAPAN
81.(0)42.775.3011 TEL • 81.(0)42.775.3015 FAX • INFO@EVERPURE.CO.JP EMAIL

EVERPURE-SHURFLO SOUTHEAST ASIA, 390 HAVELOCK ROAD, #04-01, KING'S CENTRE, SINGAPORE 169662
65.6795.2213 TEL • FAX: 65.6795.2219 FAX • CSEVERPURE@PENTAIR.COM EMAIL

All Pentair trademarks and logos are owned by Pentair, Inc. All other brand or product names are trademarks or registered marks of their respective owners. Because we are continuously improving our products and services, Pentair reserves the right to change specifications without prior notice. Pentair is an equal opportunity employer.